GODDRES PHARMACEUTICALS PVT. LTD.

Date: 19-10-2026

To,
The Architect / Project Consultant
Office Renovation & Repair Works - Goddres Pharmaceuticals Pvt. Ltd.

Subject: Counter-offer against contractor's estimate dated 16-10-2026 for renovation & repair works

Dear Sir / Madam,

We have reviewed the contractor's estimate of Rs 8,80,125 + GST. We wish to proceed with the work, subject to the revised rates, clarifications and terms below. The detailed revised BOQ is attached. We request you to take this up with the contractor and share their revised offer.

1. Revised commercial offer (excluding GST)

Section	Quoted (Rs)	Revised (Rs)
A. Carpentry & partition work	4,69,500	3,69,200
B. Painting work	2,55,000	1,75,000
C. Electrical work	40,000	31,000
D. Flooring work	1,15,625	1,01,250
Total (excl. GST)	**8,80,125**	**6,76,450**

GST @ 18% extra as applicable. Provisional items (minor repairs, panel lights) are paid on actuals, only with prior written approval.

2. Key revisions and clarifications required

- **Painting quantity:** the quoted 5,000 sq ft of gypsum ceiling is about 4.4 times the flooring area (1,125 sq ft). Quantity to be jointly measured. Revised rate Rs 32/sq ft for putty touch-up, 1 primer coat and 2 finish coats.
- **Gypsum partition:** to be measured as wall area with both faces included. Please confirm whether the "x 2" in 8 x 9.5 x 2 means two faces (then billable quantity is 76 sq ft) or two partitions. Partition without glass wool to be priced lower than with glass wool.
- **Shutters on existing frames (Rs 800 -> 600/sq ft) and column cladding (Rs 800 -> 550/sq ft):** no new carcass is involved, so the rates should be well below a full cupboard (Rs 1,100-1,235/sq ft).
- **Workstations:** Rs 24,000 per unit (5' x 2.5', keyboard tray, side storage, 1 mm laminate).
- **Lump sums:** glass doors, electrical shifting and cleaning to be broken up into quantity x rate, with specifications. Carpet removal to be included in the flooring rate.
- **Specifications:** BWR ply (IS:303), 1 mm laminate (Merino/Greenlam), Hettich/Ebco hardware, Gyproc board, Asian Paints Royale Luster, 12 mm toughened glass with floor spring, FR wires (Polycab/Finolex), Anchor/Legrand switches, vinyl with min. 0.3 mm wear layer. Substitutions only with approval.

3. Commercial terms

- Rates fixed for the contract. Payment on final joint measurement, not exceeding BOQ quantities without written approval. Note 9 ("amount may vary") to apply only to reductions.
- Payment: 15% advance | 40% on completion of carpentry & partitions | 25% on completion of painting & flooring | 10% on handover & snag clearance | 10% retention released after 6-month defect liability period.
- Completion within 30 days of start. Delay penalty 0.5% of contract value per week, capped at 5%.
- Debris removal, protection of existing furniture/floors and final cleaning are included in the rates. Exclusions as per the original quote (permissions, loose furniture, plumbing, HVAC, networking/CCTV) remain.

We look forward to the contractor's revised offer on this basis so that the work order can be issued.

For Goddres Pharmaceuticals Pvt. Ltd.

Authorised Signatory
Name / Designation: _____

Encl.: Revised BOQ (Goddres_Revised_BOQ.xlsx / .pdf)