GODDRES PHARMACEUTICALS PVT. LTD. - OFFICE RENOVATION & REPAIR WORKS

Revised Bill of Quantities (Owner's counter-proposal) against contractor's estimate dated 16-10-2026

Date: 19-10-2026

Sr.	Description of work	Unit	Qty	Quoted rate (Rs)	Quoted amount (Rs)	Revised rate (Rs)	Revised amount (Rs)	Difference (Rs)	% change	Remarks / basis
A	**CARPENTRY & PARTITION WORK**									
A1	New seamless shutters / facia to existing aluminium-framed storage doors, 1 mm laminate finish, Hettich/Ebco hinges & handles	sq ft	156	800	124,800	600	93,600	-31,200	-25%	Existing frame/carcass retained; shutter-only work priced below full storage (A2).
A2	Complete new filing cupboard, 18 mm BWR ply (IS:303) carcass, 1 mm laminate outside, 0.8 mm liner inside, Hettich/Ebco hardware	sq ft	60	1,235	74,100	1,100	66,000	-8,100	-11%	Measured on front elevation area.
A3	Leakage checking & rectification	-								Owner scope - excluded from this contract.
A4	Gypsum partition with 50 mm glass wool, Gyproc board both faces on GI framing, jointing & taping complete - Cabins 1/2/3/4	sq ft	152	250	38,000	200	30,400	-7,600	-20%	To be measured as WALL AREA, both faces inclusive. If 152 sq ft = 76 sq ft x 2 faces, billable qty is 76 sq ft.
A5	Gypsum partition without glass wool, both faces - Cabins 1/2/3/4	sq ft	32	250	8,000	175	5,600	-2,400	-30%	Lower rate as no glass wool. Same wall-area measurement rule as A4.
A6	New glass partition + glass door, Cabins 1/2/3/4 (3.5'x8' + 3'x8' per cabin), 12 mm toughened glass, patch fittings, floor spring (Dorma/Ozone/Hafele), SS handle	set	4	11,250	45,000	10,000	40,000	-5,000	-11%	Original quoted as lump sum Rs 45,000 (shown as 4 sets for comparison). Glass make & fittings to be confirmed.
A7	Workstation 5' x 2.5' with keyboard tray & side storage, 1 mm white laminate	nos	3	30,000	90,000	24,000	72,000	-18,000	-20%	Price incl. modesty panel, wire manager & grommets.
A8	Laminate allowance: 1 mm laminate @ Rs 1,500-1,600 per sheet (Merino / Greenlam / equivalent)	-								Specification only. Credit/debit for any change in selected laminate.
A9	Minor repairs to damaged ceiling / light cut-outs	-								Provisional - on actuals, with prior written approval only. Not to exceed Rs 10,000 without approval.
A10	Remove old fabric from columns and clad with ply + 1 mm laminate	sq ft	112	800	89,600	550	61,600	-28,000	-31%	Includes removal & disposal of old fabric.
	TOTAL - CARPENTRY & PARTITION WORK				**469,500**		**369,200**	**-100,300**	-21%	
B	**PAINTING WORK**									
B1	Asian Paints Royale Luster (or equiv.) on gypsum ceiling only (excl. Armstrong 2'x2' ceiling): putty touch-up, 1 coat primer, 2 coats finish	sq ft	5,000	45	225,000	32	160,000	-65,000	-29%	QUANTITY TO BE JOINTLY MEASURED - quoted area (5,000 sq ft) is ~4.4x the flooring area (1,125 sq ft).
B2	Deep cleaning, covering & protection of existing furniture / floor during works	LS	1	30,000	30,000	15,000	15,000	-15,000	-50%	Includes final handover cleaning.
	TOTAL - PAINTING WORK				**255,000**		**175,000**	**-80,000**	-31%	
C	**ELECTRICAL WORK**									
C1	Shifting of points in Cabins 1/2/3 in PVC casing-capping with matching modular switches (Anchor/Legrand), FR wires (Polycab/Finolex)	LS	1	40,000	40,000	31,000	31,000	-9,000	-23%	Contractor to provide point count. Alternatively Rs 1,000 per point on joint count, whichever is lower.

Sr.	Description of work	Unit	Qty	Quoted rate (Rs)	Quoted amount (Rs)	Revised rate (Rs)	Revised amount (Rs)	Difference (Rs)	% change	Remarks / basis
C2	Replacement of non-working 2'x2' LED panel lights (Philips/Wipro/Syska, 36-40 W)	nos				1,500				Original quote: 'BALANCE' (unpriced). Rate per panel, supply & fix; qty on joint count.
	TOTAL - ELECTRICAL WORK				**40,000**		**31,000**	**-9,000**	-23%	
D	**FLOORING WORK**									
D1	Removing old carpet incl. adhesive scraping & debris disposal	LS	1	6,500	6,500	-	-	-6,500	-100%	To be included in D2 rate.
D2	Supply & fix 2 mm vinyl plank flooring (min. 0.3 mm wear layer, brand to be approved) incl. levelling, skirting/beading	sq ft	1,125	97	109,125	90	101,250	-7,875	-7%	Alt: carpet tiles at Rs 110-115 if selected.
	TOTAL - FLOORING WORK				**115,625**		**101,250**	**-14,375**	-12%	
	GRAND TOTAL (excl. GST)				**880,125**		**676,450**	**-203,675**	-23%	
	GST @ 18%				158,423		121,761	-36,662	-23%	
	GRAND TOTAL (incl. GST)				**1,038,548**		**798,211**	**-240,337**	-23%	

NOTES & CONDITIONS

All rates exclude GST @ 18%, which is shown separately.

1 Rates are FIXED for the duration of work. Payment on final joint measurement; quantities shall not exceed this BOQ without written approval.

2 Provisional items (A9, C2) are paid only on actuals with prior written approval.

3 Debris removal from site, protection of existing items and final cleaning are included.

4 Exclusions retained from original quote: BMC/society permissions, loose furniture & blinds, old furniture shifting, leakage/plumbing, HVAC, networking/CCTV.

5 Material makes/brands as specified; any substitution only with prior approval of Architect/Owner.

6

Section-wise comparison

Section	Quoted (Rs)	Revised (Rs)	Difference (Rs)	% change
A. Carpentry & Partition Work	469,500	369,200	-100,300	-21%
B. Painting Work	255,000	175,000	-80,000	-31%
C. Electrical Work	40,000	31,000	-9,000	-23%
D. Flooring Work	115,625	101,250	-14,375	-12%
Total excl. GST	880,125	676,450	-203,675	-23%
GST @ 18%	158,423	121,761	-36,662	-23%
Total incl. GST	1,038,548	798,211	-240,337	-23%